GTC Plant Enquiry. Our Ref 6687533, Your Ref N/A generated for navneet.chhabra@mgroupltd.com at 09/06/2026 11:18:19. This drawing is reproduced from our records archive at the time of enquiry.


Jenner Road
Jenner Road
Jenner Road
Harvey Road
Harvey Road
Harvey Road
Harvey Road
Harvey Road
Harvey Road
Harvey Road
Simpson Place
Kilner Road
Mandeville Road
Mandeville Road
Mandeville Road
Mandeville Road
Blenheim Place
Barnard Crescent
Barnard Crescent
Guttmann Road
Haslerig Close
Hancock Close
Hancock Close
Hancock Close
Foskett Way
Foskett Way
Foskett Way
Foskett Way
Foskett Way
Foskett Way
Foskett Way
Emmett Drive
Emmett Drive
Walker Place
Fuggle Drive
Fuggle Drive
Whiskin Lane
Baynton Road
Baynton Road
Rutherford Road
N7040117-2
N7040117-1
N8023240-1
N9001214-1
N7042166-1
Meter 1 K28
Meter 2 K28
Meter 1 K76
Meter 2 K76
Meter 1 K124
Meter 2 K124
1 SIV 50mm Open In Chamber
2 SIV 50mm Open In Chamber
3 SIV 50mm Open In Chamber
4 SIV 50mm Open In Chamber
5 SIV 50mm Open In Chamber
90mm LP PE80
63mm LP PE80
125mm LP PE80
180mm LP PE80
25mm LP PE80
90mm LP PE80 ASSUMEDROUTE
SGN 125mm LP PE80
N7040117
482365,212001
Unit 1
7.8m
3.6m
Slope
0
13 m

N7040117 - Recent revisions

N7040117/gas		Revision History		
Rev	Comment	Date	Dsg.	App.
3.0	N9001214-1 Import 9/12/24	10/12/24	CF	CF
2.0	(Legacy) 1708m of gas mains added 1628m of gas mains removed 167 g ...	13/12/18	CC	CC
1.0	(Legacy) 1580m of gas mains added 1 CSEPs added	08/03/17	HS	HS

N7040117_E1 HP21 9AB

NOTES FOR DWELLINGS WITH MULTI-OCCUPANCY

Gas service pipes, to, on or in flats and other multi-occupancy premises with two or more floor above the ground floor shall be constructed in compliance with The Latest Editions Of:

E S20 (INCORPORATING GAS INTO FLATS AND OTHER BUILDING COMPLEXES)

E S21 (CONSTRUCTION SPECIFICATION FOR SERVICES, RISERS AND LATERALS IN FLATS AND OTHER MULTI-OCCUPANCY BUILDINGS)

E S22 (MANUFACTURING SPECIFICATION FOR PE-IN-STEEL SERVICE ENTRIES)

Particularly note that:

1. Voids containing gas service pipes must be adequately ventilated to the outside atmosphere by natural means.

2. Multiple meter installations within a meter room must be naturally ventilated to the outside atmosphere at high and low level. The requirements are that ventilation must be not less than 2% of the internal floor area or its notional equivalent of 0.5m2 per meter (20 Gas Meter Positions x 0.5 m2 = 10 m2 (x 2%) = 0.2 m2), equally shared between high and low level. If ventilation is provided in only one wall, then the minimum value shall increase to 3% of the respective area.

3. If ventilation is provided by one or more ducts, the duct(s) should have a fire resistance at least equal to the highest standard required for any of the fire resisting divisions it crosses.

4. Meters, meter cupboards & meter rooms must NOT be installed or constructed in any area that has openings on to what is deemed the sole means of escape and where the consequences of fire or explosion at the meter would compromise the integrity of the building structure.

5. If meters are to be fitted into a bin store or other such area, which is not a dedicated meter room, then the developer will be required to provide a compound area for protection from damage and tampering, with each consumer being provided with a suitably labelled key.

6. Internal and external isolation valves must be accessible at all times.

7. Ducts for gas risers and entries must be ventilated top and bottom to the outside air. The cross-sectional free airspace must be 0.05m2 for each opening. Ducts and vent must conform to BS8313.

If you are not in possession of the above referenced documents, please call your respective call centre number and request a copy.

N7040117_E2 HP21 9FG


C9
PE FULL BORE CUT OUT (UP TO AND INCLUDING 180mm) - TWO WAY SQUEEZE OFF INSERT TEE
BYPASS
BYPASS DIMENSIONS
P/POINT
P/POINT
MAIN
TWO WAY SQUEEZE OFF + CUT IN PE TEE TO EXISTING PE MAIN
125mm PE x 180mm PE TEE

N7040117_temp-3f2c74f1-8d4d-46ef-a080-c2d13ba8c534 HP21 9AB

GROUND MOUNTED ME
Cavity boxes to be installed as standar

10-12-2024

This design is across multiple drawings for details please refer to all drawings.

Gas Notes
All gas mains and ducts that shall contain a gas main must be overlaid with gas identifiable maker tape 250mm above the apparatus. All gas services and ducts that shall contain a gas service must be overlaid with gas identifiable maker tape 75mm above the apparatus. All gas pipes and ducts that shall contain a gas pipe should have a minimum of 250mm clearance from other utilities.

Maximum Proximity to Properties

Diameter of main (mm)	Minimum Building Proximity (m)			
	<0.075 bar	>0.075 bar ≤ 2 bar	> 2 bar ≤ 5.5 bar	> 5.5 bar ≤ 7 bar
Up to 125	0.25	2	4	6
126 to 355	1	2	4	6
356 to 500	1	2	4	8
501 to 1000	1	5	13	15

Ducting Specification

- Ducting for mains must be yellow and non-perforated and only used perpendicular carriageway crossings.
- Ducting for services must be yellow and perforated along it's entire length.
- Only one pipe is allowed per duct.

Gas Pipe External Diameter	Duct Inside Diameter
25mm & 32mm	60mm
63mm	100mm
90mm	150mm
125mm	200mm
180mm	300mm
250mm & 315mm	400mm

Meter Positions
For all meter box types any position where damage could occour, especially from vehicles, shall be avoided.
Semi concealed Universal meter boxes shall not:

- Obstruct footpaths
- Passageways
- Drives
- Be a trip hazard

Material Specification
For material specifications please refer to GG-PSC-ES-0002 Gas Materials Purchase - Standards & Specifications

Excavation Carried Out by BUUK
The trenches highlighted in blue will be excavated and reinstated by BUUK contractors, the excavation and reinstatement of the other trenches will be the responsibility of the customer.

	Proposed	Laid
HP Piepe > 7bar	– – – – –	———
IP Pipe 2bar - 7bar	– – – – –	———
MP Pipe 0.75 - 2bar	– – – – –	———
LP Pipe < 0.75mbar	– – – – –	———
Service Pipe	– – – – –	———
Ducted Pipe	———	
Excavate by buuk Contractors	———	
Asset Boundary	———	
Connection Point	CP	
Pressure Reduction Station		
Reducer		
Open / Closed Valve	⊗ / ⊗	
Network Boundary Point	NBP	
Other IGT Boundary	▭	
Abandoned	///	
To Disconnect	✕✕✕	

Semi Concealed	S
Cavity	C
Internal	I
Kisosk	K
Manifold	M
Point Load	P
Unibox	U
Surface Mouted	W
End Cap	]

Plan Notes
This plan shows apparatus owned by the BUUK Group. Any third party apparatus indicated on these drawings is shown for indicative purposes only. The information shown on this plan is given without warranty, the accuracy cannot be guarenteed. No liability of any kind whatsoever is accepted by the company. Safe digging practices, in accordance with HS(G)47, must be used to verify and establish the actual position of apparatus. This plan is reproduced by the permission of Ordnance Survey on behalf of HMSO. © Crown copyright and database right 2007. All rights reserved Ordnance Survey Licence number 0100021063.

Developers Responsibility
When apparatus have been laid it becomes the responsibility of the developer to ensure it is suitably protected, therefire backfilling should be carried out as soon as possible. Replacement and repair of damaged apparatus, including administrative costs will be fully recharged to the developer. It will be the developer's responsibilityto recover the costs from the third parties.

Revision Notes
For a revision history of this network design please see seperate revision history document.

GTC, Woolpit Business Park,
Suffolk,
IP30 9UP

Tel: 01359 240363
www.gtc-uk.co.uk

Last Edit By:	
Last Approved By CRAIG CLAYDON	

18

Approved

OS Ref: 482508,212141

Location: Stoke Mandeville Hospital Site

Developer/Client: Persimmon Homes

Drawing Number/Title: N7040117-1_1_of_1_Rev3-0_appendix

Network Number:	Project Number:
N7040117	N7040117-1

Scale:	Sheet Size:	Revision:
1:500	A0	3-0